280

NOTICE.

Owing to the large number of applications received from candidates to join the Sanitary Inspectors' and Vaccinators' classes it is not possible to acknowledge receipt of all the applications. But each candidate will have as soon as possible an intimation regarding the starting of the classes, addressed to him personally, and as to whether or not his application has been entertained for admission, as the numbers must unfortunately be limited.

G. S. DAVID,
For *Sanitary Commissioner.*

MYSORE DIVISION.

The 17th April 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 9th May 1908 for improving the Bheriya tank, Registered No. 5, Yedatore Taluk. For other particulars see *Mysore Gazette* No. 17, dated 23rd April 1908

WATER-SUPPLY AND STORES DIVISION.

Dated 28th April 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Water-Supply and Stores Division, up to 15th May 1908, for (1) constructing motor and pump house and foundations to motor and pumps, (2) constructing Chief Operator's and Operator's quarters and (3) dismantling the existing Driver's quarters at Belagola, Seringapatam Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. Chief Operator's and Operator's quarters should be completed by the end of August 1908, and other works by the end of October 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing motor and pump house, etc., at Belagola, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items	Per	Constructing mortar and pump house	Constructing foundation to mortar	Constructing Chief operator's quarters	Constructing operator's quarters
		Quantity	Quantity	Quantity	Quantity
Earthwork excavation	C. yds.	124	6	25	60
Concrete in mortar	C. ft.	759	...	...	..
Burnt brick in clay	do		...	1,005	3554
Burnt brick in mortar	do	4,347	...	1,340	2912
Arch work burnt brick in mortar ...	do	78	...	...	...
Burnt stone slabs, 6" thick, dressed ...	S. ft.	190	...	105	188
Plastering with chunam	Sqr.	45·46	...	16·04	27·09
Colour washing	do	21·57	...	16·04	27·09
White washing	do	23·89	...	14·53	37·43
Cement pointing	do	1·30	...		...
Rolled joists	Cut.	21	...	...	...
Flooring with hoordies bricks and pointing with cement.	Sqr.	4·80	...	...	...
Flooring with 1st class Basel Mission square tiles over 3" concrete bed and cement pointing.	do	5·12	...	2·00	3·90
Cornice work 1' × $\frac{3}{4}$'	R. ft.	24	...	...	...
Teakwood work with wood oiling ...	C. ft.	33·18	...	48·43	79·14
Roofing with corrugated zinc sheet ...	Sqr.	18·32	...	...	.
Teakwood door pannelled	S. ft.	48	...	...	...
Teakwood windows with iron bars venetian and glazed shutter.	do	360	..	...	..
Teakwood circular ventilator with iron bar and glazed shutter.	do	3·14	...	...	...
Painting with Dado	Sqr.	11·88	...	...	..
Galvanized ridge coping	R ft.	71	..	...	...
Teakwood eave boards ornamental ...	do	179	...	46	94
Teakwood finials	No.	4		8	6
Burnt brick in cement	C ft	...	193	..	...
Burnt stone slabs 8" thick dressed ...	S. ft.	...	83	...	..
Drilling holes to bed slabs	No.	...	14	...	...
Cutting grooves on top of pillars ...	do	...	...	2	...
Copying with burnt brick in chunam and chunam plastering.	R. ft.	...	...	70	160
Plasterings with mud ..	Sqr.	...	...	14·53	37·43
Cuddapa slab flooring over 3" sand bed with cement pointing.	do	...	...	1·20	..
Roofing with 1st class Mangalore tiles with teak reepers and chunam borders.	do	...	...	7.69	17·50
Teakwood doors, battened	S. ft.	...	..	104	257
Teakwood windows with iron bars and pannelled shutters.	do	...	...	72	59
Chacolate painting	Sqr.	...	..	2·88	7·74
Filling with earth and watering and tamping	C. ft.	...	...	11	28
Bengal Terrace ...	Sqr.	...	..	...	·48
Pointing with chunam	do	...	...	...	1·46
Cost of erecting corrugated zinc sheet ...	Item	1	...	...	...

V. RANGASWAMI IYENGAR,
Executive Engineer.